



# Kyushu University new campus plan



Fukuoka City

# Center for Accelerator and Beam Applied Science of Kyushu University

## 1<sup>st</sup> stage (2007~)

relocation of engineering related faculties (2005, 2006)



Cockcroft-Walton accelerator laboratory (Faculty of Engineering)



<sup>60</sup>Co gamma-source (Institute for irradiation and analysis of quantum radiation)

## 2<sup>nd</sup> stage (2013~)

relocation of science related faculties (2015)



10 MV tandem accelerator laboratory (Faculty of Sciences)

Hakozaki campus


## New Accelerator Facility on Ito Campus



Main accelerator: 150 MeV FFAG Accelerator



New <sup>60</sup>Co gamma-source (185 TBq)

8 MV tandem accelerator (NEC Pelletron 8UDH)






# Access to the Ito Campus



- Expressway
- Fukuoka Expressway
- Fukuoka City Subway Kuko Line
- Fukuoka City Subway Hakozaki Line
- Fukuoka City Subway Nanakuma Line
- JR
- Nishitetsu Tenjin Omuta Line

# Ito campus



Humanities related  
Faculties  
(Plan)

Faculty of  
Sciences


Center for Accelerator  
And Beam Applied Science

General  
undergraduate  
education


Faculty of  
Engineering

Faculty of  
Agriculture  
(Plan)

Largest campus in Japan




# Accelerator Facility of Kyushu University



# 150 MeV FFAG Accelerator

(developed by Prof. Mori and others at KEK)

The prototype machine for various applications such as ADS, cancer therapy, etc.



Moved to Kyushu University

Researchers working for the development of the FFAG:

Y. Yonemura, H. Arima, students (H. Okita, N. Motohashi...), N. Ikeda  
Y. Mori

# Tandem Accelerator



## Parameters of Tandem Accelerator


Accelerator Type	Horizontal Tandem Van de Graaff
Model	National Electrostatics Corp. (NEC) , Pelletron 8UDH
Terminal Voltage	max. 8 MV (stable operation up to 7 MV)
Accelerator Tank	Diameter: 3.0 m / Length: 13.6 m
Insulation Gas	SF <sub>6</sub> (Pressure: 0.6 MPa)
Ion Source	Sputter Ion Source or RF Ion Source
Beam Current	Proton 1 nA (in the 1 <sup>st</sup> stage) (1 μA in near future)
Terminal Stripper	C Foil and N <sub>2</sub> Gas
Charging Device	Double Pellet Chains (Current: 150 mA × 2)

# Tandem Accelerator


The tandem accelerator will be employed as a heavy ion injector to the 150 MeV FFAG



Accelerator disassembled at Kyoto University



Moved to Kyushu University




Beams from the tandem accelerator will also be used for AMS, nuclear physics experiment, and so on.




Researchers working at tandem accelerator facility:  
 staffs of faculty of sciences;  
 T. Noro, T. Teranishi, T. Wakasa, ...

# Present beam line configuration of Center for Accelerator and Beam Applied Science of Kyushu University






charge exchange  
injection system  
for positive ion beams






Beam injection line



Beam injection line

# charge exchange injection system from tandem accelerator













Present beam line

Future plan


# Tandem – FFAG complex

Injector	Baby Cyclotron	Tandem Accelerator
Particle	Proton	Heavy Ion ( ${}^A_ZX^{q+}$ )
E/A	12 → 150 MeV (10 → 125 MeV)	$12 \left(\frac{q}{A}\right)^2 \rightarrow 160 \left(\frac{q}{A}\right)^2$ MeV/u 3 MeV/u → 40 MeV/u for fully stripped light-heavy ions
Revolution Frequency	1.6 → 4.6 MHz	$1.6 \frac{q}{A} \sim 5.7 \frac{q}{A}$ MHz
Repetition Rate	100 Hz	100 Hz


# Energy of Heavy Ion versus Terminal Voltage




# Present beam lines



# Construction Plan (2017 ~ ?)



# vertical beam line for irradiation, neutron production, and so on



# Collaborators

## FFAG R&D

Faculty of Eng., Kyushu Univ. : Y. Yonemura, H. Arima,  
Students (H. Okita, N. Motohashi...)

Res. Reactor Inst., Kyoto Univ.: Y. Mori

KEK: A. Takagi, H. Nakayama

## Tandem Accelerator facility

Faculty of Sci., Kyushu Univ.: T. Noro, T. Teranishi, T. Wakasa,  
S. Sakaguchi, K. Fujita

## Radiation safety, future plan, etc.

Faculty of Eng., Kyushu Univ. : K. Ishibashi, Y. Uozumi, N. Shigyo  
(Faculty of Sci., Kyushu Univ.: T. Noro, T. Teranishi)

# Construction and Beam Commissioning log

2008      2009      2010      2011      2012      2013      2014      2015      2016

**1<sup>st</sup> stage**  
2008 ~ 2011



**1.5 stage**  
2011 ~ 2013



**2<sup>nd</sup> stage**  
2014 ~



**Cyclotron**

Maintenance & Reassembling (2008.9 - 2009.3) ←→

Beam commissioning ←→

Radiation Inspection (2014. 6) ←→

In Operation ←

**FFAG**

Construction FFAG (2009.5 - 2012. 2) ←→

Test of Power sources & Beam injection (2011.12 - 2012. 12) ←→

Beam Acceleration (2013.7 - 2015. 12) ←→

In Operation ←

Construction of beam line ←→

**Tandem**

Construction of Tandem (2011.3 - 2013. 6) ←→

Radiation Inspection (2014. 9 and 2015 6) ←→

Beam commissioning (2014.4 - 2015.6) ←→

In Operation ←